



Southworth Dura Dock Installation

1. The power unit will be positioned and properly lagged down inside the facility by the installer.
2. An electrician will make the necessary (necessary or permanent) electrical connections and run the power unit. Southworth to provide the pushbutton and motor starter prewired to the control panel.
3. The installer will offload and will set the lift into position onto the preformed concrete slab on into the concrete pit.
4. The hydraulic line between the power unit and lift will be installed.
5. If the hydraulic line is not in conduit, an inverted "C" channel or other protective device will be placed over the hydraulic line.
6. The lift will be lagged down into position.
7. If equipped, the ramp will be lagged down into position.
8. The bridge plate will be installed on the end of the platform.
9. Handrails and snap chains will be installed on the platform.
10. The lift will be inspected and cycle tested.
11. The area will be cleaned of debris; lift wiped and touched up where paint may have been scratched.